



STATE OF IDAHO
DEPARTMENT OF
ENVIRONMENTAL QUALITY

1445 North Orchard • Boise, Idaho 83706-2239 • (208) 373-0550

Dirk Kempthorne, Governor
C. Stephen Allred, Director

January 17, 2001

CERTIFIED MAIL # 7099 3220 0006 2681 7699

Mr. Kelly Erickson
Supervisor
Washington County Road & Bridge
P.O. BOX 813
Weiser, ID 83672

RE: P-000709, Washington County Road & Bridge, Weiser
(Portable Rock Crushing Facility, Permit to Construct No. 777-00279)

Dear Mr. Erickson:

On October 26, 2000, the Idaho Department of Environmental Quality (DEQ) received a Permit to Construct application from Washington County Road and Bridge for a portable rock crushing facility located at Washington County Road & Bridge's Fox Pit near Cambridge, Idaho. Based on review of the application and all applicable state and federal rules and regulations, DEQ finds that this project meets the provisions of IDAPA 58.01.01.200 (*Rules for the Control of Air Pollution in Idaho*). Enclosed is PTC No. 777-00279 for the portable rock crushing facility.

Enclosed is a copy of the Portable Equipment Registration and Relocation Form that is required to be completed and submitted to DEQ at least ten (10) days prior to relocation of any equipment covered by this permit. Also enclosed are copies of maps showing all nonattainment areas within the state of Idaho.

This permit does not release the Permittee from compliance with all other applicable federal, state, local, or tribal laws, regulations, or ordinances. With regard to collocation with another portable facility, conservative assumptions were used to derive the throughput limitations. If this throughput is too restrictive for a particular project, contact DEQ prior to collocation and request a detailed site-specific analysis.

Please pay particular attention to the reporting requirements contained in Paragraph E of the General Provisions section of the permit. This information is needed to properly track the progress of the permit. Please refer to the appropriate permit number when submitting reports required in the Reporting Requirements section of the permit.


You are strongly encouraged to request a meeting with DEQ to discuss the permit terms and requirements with which your facility must comply. Mr. Thomas Krinke of the Boise Regional Office will contact you regarding this meeting. DEQ strongly recommends that your facility's plant manager, your responsible official, environmental contact, and any operations staff responsible for day-to-day compliance with permit conditions also attend the meeting.

Mr. Kelly Erickson
January 17, 2001
Page Two

You, as well as any other entity, may have the right to appeal this final agency action pursuant to the Idaho Department of Health and Welfare Rules, Title 5, Chapter 3, "Rules Governing Contested Case Proceedings and Declaratory Rulings", by filing a petition with the Hearings Coordinator, Department of Environmental Quality, 1410 N. Hilton St., Boise, ID 38706-1255, within thirty-five (35) days of the date of this decision. However, DEQ encourages you to contact the Air Quality Permit Program to address any concerns you may have with the enclosed permit prior to filing a petition for a contested case.

If you have any questions regarding the terms or conditions of the enclosed permit, please contact Thomas Krinke, at (208) 373-0550.

Sincerely,



Stephen E. West
Regional Administrator
Boise Regional Office

SEW:AJ/ls:CM P187.4005 G:\AHWUJOHNSON\PTCIWASH_COUNTY\000709_PL.DOC

Enclosures

cc: DEQ State Office
Boise Regional Office

State of Idaho
Department of Environmental Quality

**PERMIT TO CONSTRUCT
AN AIR POLLUTION
EMITTING SOURCE**

PERMIT NUMBER

7 7 7 - 0 0 2 7 9

AQCR

CLASS

S M

SIC

1 4 4 2

ZONE

UTM COORDINATE (km)

1. PERMITTEE

Washington County Road & Bridge

2. PROJECT

Portable Rock Crushing Plant

3. MAILING ADDRESS

P.O. Box 813

CITY

Weiser

STATE

Idaho

ZIP CODE

83672

4. SITE LOCATION COUNTY

Portable

NO. OF FULL-TIME EMPLOYEES

2

PROPERTY AREA AT SITE (Acreage)

Varies

5. PERSON TO CONTACT

Kelly Erickson

TITLE

Supervisor

TELEPHONE

(208) 549-0950

6. EXACT PLANT LOCATION

Portable

7. GENERAL NATURE OF BUSINESS & KINDS OF PRODUCTS

Rock Crushing (Including Aggregate, Asphalt, and Concrete Production when Collocated)

8. GENERAL CONDITIONS


This permit is issued according to the *Rules for the Control of Air Pollution in Idaho*, Section 58.01.01.200, and pertains only to emissions of air contaminants that are regulated by the State of Idaho and to the sources specifically allowed to be constructed by this permit.

This permit (a) does not affect the title of the premises upon which the equipment is to be located, (b) does not release the Permittee from any liability for any loss due to damage to person or property caused by, resulting from, or arising out of the design, installation, maintenance, or operation of the proposed equipment, (c) does not release the Permittee from compliance with other applicable federal, state, tribal, or local laws, regulations, or ordinances, (d) in no manner implies or suggests that the Idaho Department of Environmental Quality (DEQ) or its officers, agents, or employees, assumes any liability, directly or indirectly, for any loss due to damage to person or property caused by, resulting from, or arising out of design, installation, maintenance, or operation of the proposed equipment.

This permit is not transferable to another person, place, piece, or set of equipment. This permit will expire if construction has not begun within two years of its issue date or if construction is suspended for one year.

This permit has been granted on the basis of design information presented with its application. Changes of design or equipment may require Department approval pursuant to the *Rules for the Control of Air Pollution in Idaho*, IDAPA 58.01.01.200, et.seq.

DISCLAIMER: This document may serve as a Preliminary Inspection Finding Form for use by Department personnel in communicating your compliance status upon inspection. It does not constitute a final determination of compliance status with the Idaho Code or any rules promulgated, permits issued, or consent or judicial orders entered into pursuant to the law. The Idaho Department of Environmental Quality reserves the right to supplement this document with additional compliance determinations, and amend, change, or otherwise modify any compliance determination stated in this document. This document in no way restricts the State of Idaho Department of Environmental Quality from taking any action available under law to address past, present, or future violations of the laws administered by the agency.


ADMINISTRATOR, BOISE REGIONAL OFFICE
DEPARTMENT OF ENVIRONMENTAL QUALITY

DATE:

1/17/2001

Permittee: Washington County Road & Bridge Project: Rock Crushing Plant Location: Portable Source: Portable Rock Crushing Plant	PERMIT NUMBER <table border="1" style="margin: 0 auto; border-collapse: collapse;"> <tr> <td style="padding: 2px 5px;">7</td> <td style="padding: 2px 5px;">7</td> <td style="padding: 2px 5px;">7</td> <td style="padding: 2px 5px;">-</td> <td style="padding: 2px 5px;">0</td> <td style="padding: 2px 5px;">0</td> <td style="padding: 2px 5px;">2</td> <td style="padding: 2px 5px;">7</td> <td style="padding: 2px 5px;">9</td> </tr> </table>	7	7	7	-	0	0	2	7	9
7	7	7	-	0	0	2	7	9		

FOR DEQ USE ONLY

IN	OUT	PEND	UNK

A. STATEWIDE REQUIREMENTS

The Permittee shall comply with the following source wide conditions when the rock crushing facility is operated anywhere (nonattainment, attainment, or unclassifiable areas) within the state of Idaho.

A.1 EMISSION LIMITS

A.1.1 Crusher Opacity Limit

Particulate matter (PM) emissions from portable rock crushers shall not exhibit more than fifteen percent (15%) opacity. Opacity shall be determined using the procedures specified in IDAPA 58.01.01.625 (*Rules for the Control of Air Pollution in Idaho*).

A.1.2 Transfer Point Opacity Limit

PM emissions from any transfer point on belt conveyors, or from each grinding mill, screening operation, bucket elevator, belt conveyor bagging operation, storage bin, enclosed truck, or rail car loading station shall not exhibit greater than ten percent (10%) opacity. Opacity shall be determined using the procedures specified in IDAPA 58.01.01.625.

A.1.3 Opacity Limit

Emissions emanating from any stack, vent, or other functionally equivalent opening, shall not exceed twenty percent (20%) opacity for a period or periods aggregating more than three (3) minutes in any sixty (60) minute period as required in IDAPA 58.01.01.625. Opacity shall be determined using the procedures contained in IDAPA 58.01.01.625.

A.1.4 Visible Emission Limits at Property Boundary

Fugitive emissions shall not be observed leaving the property boundary for a period or periods aggregating more than three (3) minutes in any sixty (60) minute period. Visible emissions shall be determined by EPA Reference Method 22, as described in Appendix A of 40 CFR Part 60, or a DEQ-approved alternative method.

A.2 OPERATING REQUIREMENTS

A.2.1 Number of Crushers and Generators

The rock crushing facility shall not use more than two (2) crushers and one (1) four hundred sixty kilowatt (460-kW) generator.

Inspection Comments:

DATE:

Permittee: Washington County Road & Bridge
 Project: Rock Crushing Plant
 Location: Portable
 Source: Portable Rock Crushing Plant

PERMIT NUMBER

7 7 7 - 0 0 2 7 9

FOR DEQ USE ONLY

IN	OUT	PEND	UNK

A.2.2 Reasonable Control of Fugitive Emissions

All reasonable precautions shall be taken to prevent PM from becoming airborne as required in IDAPA 58.01.01.651. In determining what is reasonable, considerations will be given to factors such as the proximity of dust-emitting operations to human habitations and/or activities and atmospheric conditions which might affect the movement of PM. Some of the reasonable precautions include, but are not limited to, the following:

- A.2.2.1 Use, where practical, of water or chemicals for control of dust in the demolition of existing buildings or structures, construction operations, the grading of roads, or the clearing of lands;
- A.2.2.2 Application, where practical, of asphalt, water, or suitable chemicals to dirt roads, material stockpiles, and other surfaces which can create dust;
- A.2.2.3 Installation and use, where practical, of hoods, fans, and fabric filters or equivalent systems to enclose and vent the handling of dusty materials. Adequate containment methods should be employed during sandblasting or other operations;
- A.2.2.4 Covering, where practical, of open-bodied trucks transporting materials likely to give rise to airborne dusts;
- A.2.2.5 Paving of roadways and their maintenance in a clean condition, where practical; or
- A.2.2.6 Prompt removal of earth or other stored material from streets, where practical.

A.2.3 Fugitive Dust Control Plan

Within sixty (60) days of issuance of the permit, the permittee shall have developed and submitted to the appropriate DEQ Regional Office a Fugitive Dust Control Plan for the crushing facility. Upon DEQ approval, the Fugitive Dust Control Plan shall become an enforceable part of this permit. This plan shall include the following information:

- A.2.3.1 Identify and list all areas of operations where fugitive dust may be generated (i.e., haul roads, vehicle traffic areas, storage piles, transfer points, etc.).
- A.2.3.2 For each fugitive dust source listed, identify and describe the type of control methods and procedures to be used to control fugitive emissions (i.e., application of water or chemical dust suppressants, covering open trucks transporting dusty material, paving of roadways, etc.).

Inspection Comments:

DATE:

Permittee: Washington County Road & Bridge	PERMIT NUMBER
Project: Rock Crushing Plant	7 7 7 - 0 0 2 7 9
Location: Portable	
Source: Portable Rock Crushing Plant	

FOR DEQ USE ONLY			
IN	OUT	PEND	UNK

A.3.5 Visible Emissions Testing

The Permittee shall conduct a visual determination of emissions at the property boundary in accordance with IDAPA 58.01.01.157 and General Provision F of this permit.

A.4 REPORTING REQUIREMENTS

A.4.1 Performance Test Protocol

Prior to conducting any emission test, the Permittee is strongly encouraged to submit in writing to DEQ, at least thirty (30) days in advance, a performance test protocol in accordance with IDAPA 58.01.01.157.01.a.

A.4.2 Performance Test Report

In accordance with IDAPA 58.01.01.157.04, the Permittee shall submit a written report of the performance test results to DEQ within thirty (30) days of completion of the test.

A.4.3 Relocation

A.4.3.1 All existing portable equipment shall be registered. At least ten (10) days prior to relocation of any equipment covered by this permit, the Permittee shall submit a complete Portable Equipment Registration and Relocation Form (available on the DEQ website at: www2.state.id.us/deq/air/) in accordance with IDAPA 58.01.01.500 and a scaled plot plan to:

PERF Processing Unit
Idaho DEQ - Air Quality
1410 North Hilton
Boise, Idaho 83706-1255

A.4.3.2 The Permittee may also be required to submit a Fugitive Dust Control Plan, as described in Section A.2.3, to the DEQ Regional Office in charge of the region to which the facility wishes to relocate.

A.4.4 Certification of Documents

All documents including, but not limited to, application forms for Permits to Construct, monitoring data, supporting information, requests for confidential treatment, testing reports, and compliance certifications submitted to DEQ shall contain a certification by a responsible official. The certification shall state that, based on information and belief formed after reasonable inquiry, the statements and information in the document(s) are true, accurate, and complete.

Inspection Comments:

DATE:

Permittee: Washington County Road & Bridge
 Project: Rock Crushing Plant
 Location: Portable
 Source: Portable Rock Crushing Plant

PERMIT NUMBER

7 7 7 - 0 0 2 7 9

FOR DEQ USE ONLY

IN	OUT	PEND	UNK

B. ATTAINMENT OR UNCLASSIFIABLE AREA REQUIREMENTS WHEN NOT COLLOCATED

The Permittee shall comply with the conditions in Section A of this permit and the following permit conditions when the rock crushing facility is operated in any attainment or unclassifiable areas, and when it is not collocated, within the state of Idaho.

B.1 OPERATING REQUIREMENTS

B.1.1 Facility Throughput Limits

The production rate of the rock crushing facility shall not exceed a maximum of one million, four hundred nineteen thousand, one hundred twenty tons per any consecutive 12-month period (1,419,120 T/yr) when located in any attainment or unclassifiable area.

B.1.2 Collocation Requirements

When the rock crushing facility is to be collocated with another portable rock crushing plant, concrete batch plant, or hot-mix asphalt plant, the collocation requirements of Section C of this permit must be complied with.

B.1.3 Generator Hours of Operation

The generator may operate unlimited hours when located in any attainment or unclassifiable area. Therefore, no monitoring or recordkeeping are required when located in any attainment or unclassifiable area.

Inspection Comments:

DATE:

Permittee: Washington County Road & Bridge
 Project: Rock Crushing Plant
 Location: Portable
 Source: Portable Rock Crushing Plant

PERMIT NUMBER

7 7 7 - 0 0 2 7 9

FOR DEQ USE ONLY

IN	OUT	PEND	UNK

C. ATTAINMENT OR UNCLASSIFIABLE AREA REQUIREMENTS WHEN COLLOCATED

The Permittee shall comply with the conditions in Section A of this permit and the following permit conditions when the rock crushing facility is to be collocated with another portable rock crushing plant, concrete batch plant, or hot-mix asphalt plant within the state of Idaho. The rock crusher may only collocate with either one (1) portable concrete batch plant, one (1) portable hot-mix asphalt plant, or one (1) other portable rock crusher which has been permitted to specifically allow collocation.

C.1 OPERATING REQUIREMENTS

C.1.1 Collocation Areas

The rock crushing facility may collocate in attainment or unclassifiable areas only. The Permittee shall not collocate in a nonattainment area or proposed nonattainment area without obtaining a permit which specifically allows for collocation in a nonattainment area.

C.1.2 Number of Portable Sources

The rock crushing facility may only collocate with either one (1) portable concrete batch plant, one (1) portable hot-mix asphalt plant, or one (1) other portable rock crushing plant which has been permitted to specifically allow collocation.

C.1.3 Facility Throughput Limits

The production rate of the rock crushing facility shall not exceed a maximum of seven hundred nine thousand, five hundred sixty tons per any consecutive 12-month period (709,560 T/yr) when collocated with another rock crushing plant, concrete batch plant, or hot-mix asphalt plant.

C.1.4 Generator Hours of Operation

The generator shall not be operated more than five thousand, fifty-five hours per consecutive 12-month period (5,055 hr/yr) when collocated with another rock crushing plant, concrete batch plant, or hot-mix asphalt plant.

Inspection Comments:

DATE:

Permittee: Washington County Road & Bridge
 Project: Rock Crushing Plant
 Location: Portable
 Source: Portable Rock Crushing Plant

PERMIT NUMBER

7 7 7 - 0 0 2 7 9

FOR DEQ USE ONLY

IN	OUT	PEND	UNK

D. NONATTAINMENT AREA REQUIREMENTS

The Permittee shall comply with the conditions in Section A of this permit and the following permit conditions whenever the rock crushing facility is operated in areas designated as nonattainment for particulate matter with an aerodynamic diameter of less than or equal to a nominal ten (10) microns (PM-10) within the state of Idaho. While operating the rock crushing facility under the conditions set forth in Section D, the rock crusher may not collocate with any other facility.

D.1 OPERATING REQUIREMENTS

D.1.1 Facility Throughput Limits

The production rate of the rock crushing facility shall not exceed a maximum of one million, four hundred nineteen thousand, one hundred twenty tons per any consecutive 12-month period (1,419,120 T/yr) when located in any PM-10 nonattainment area or proposed PM-10 nonattainment area.

D.1.2 Collocation Requirements

The rock crushing facility shall not be collocated with another portable rock crushing, concrete batch, or hot-mix asphalt plant when located in any PM-10 nonattainment area or proposed PM-10 nonattainment area.

D.1.3 Generator Hours of Operation

The generator shall not be operated more than four thousand, nine hundred hours per any consecutive 12-month period (4,900 hr/yr) when located in any PM-10 nonattainment area or proposed PM-10 nonattainment area.

The generator shall not be operated more than thirteen and four tenths hours per day (13.4 hr/day) when located in any PM-10 nonattainment area or proposed PM-10 nonattainment area.

Inspection Comments:

DATE:

FOR DEQ USE ONLY

IN	OUT	PEND	UNK

PERMIT TO CONSTRUCT GENERAL PROVISIONS

- A. All emissions authorized herein shall be consistent with the terms and conditions of this permit and the *Rules for the Control of Air Pollution in Idaho*. The emission of any pollutant in excess of the limitations specified herein, or noncompliance with any other condition or limitation contained in this permit, shall constitute a violation of this permit and the *Rules for the Control of Air Pollution in Idaho*, and the Environmental Protection and Health Act, Idaho Code 39-101, et.seq.
- B. The Permittee shall at all times (except as provided in the *Rules for the Control of Air Pollution in Idaho*) maintain in good working order and operate as efficiently as practicable, all treatment or control facilities or systems installed or used to achieve compliance with the terms and conditions of this permit and other applicable Idaho laws for the control of air pollution.
- C. The Permittee shall allow the Director, and/or the authorized representative(s), upon the presentation of credentials:
 - 1. To enter at reasonable times upon the premises where an emission source is located, or in which any records are required to be kept under the terms and conditions of this permit; and
 - 2. At reasonable times to have access to and copy any records required to be kept under the terms and conditions of this permit, to inspect any monitoring methods required in this permit, and require stack emission testing in conformance with IDAPA 58.01.01.157 when deemed appropriate by the Director.
- D. Nothing in this permit is intended to relieve or exempt the Permittee from compliance with any applicable federal, state, or local law or regulation, except as specifically provided herein.
- E. The Permittee shall notify DEQ, in writing, of the required information for the following events within five (5) working days after occurrence:
 - 1. Initiation of Construction - Date
 - 2. Completion/Cessation of Construction - Date
 - 3. Actual Production Startup - Date
 - 4. Initial Date of Achieving Maximum Production Rate - Production Rate and Date
- F. If emission testing is specified, the Permittee must schedule such testing within sixty (60) days after achieving the maximum production rate, but not later than one hundred and eighty (180) days after initial startup. Such testing must **strictly** adhere to the procedures outlined in IDAPA 58.01.01.157, and shall not be conducted on weekends or state holidays without prior written DEQ approval. Testing procedures and specific time limitations may be modified by DEQ by prior negotiation if conditions warrant adjustment. DEQ shall be notified at least fifteen (15) days prior to the scheduled compliance test. Any records or data generated as a result of such compliance test shall be made available to DEQ upon request.

 The maximum allowable operating rate shall be limited to 120% of the average operating rate attained during any performance test period, for which a test protocol has been granted prior approval by DEQ, unless (1) the test demonstrates noncompliance, (2) a more restrictive operating limit is specified elsewhere in this permit, or (3) at such an operating rate, emissions would exceed any emission limit(s) set forth in this permit.
- G. The provisions of this permit are severable, and if any provision of this permit to any circumstance is held invalid, the application of such provision to other circumstances, and the remainder of this permit shall not be affected thereby.

Inspection Comments:

DATE: