



Idaho Department of Environmental Quality Final Section 401 Water Quality Certification

June 5, 2023

Project Name: ITD Key No. 20745; SH-55, Little Goose Creek Bridge Replacement

Permit Number: NWW-2023-00151

Applicant/Authorized Agent: Jason Brinkman – Idaho Transportation Department

Project Location: Meadow, Adams County, Idaho; 44.960085°, -116.205836°

Receiving Water Body: Little Goose Creek and associated wetlands

Pursuant to the provisions of Section 401(a)(1) of the Federal Water Pollution Control Act (Clean Water Act), as amended; 33 U.S.C. Section 1341(a)(1); and Idaho Code §§ 39-101 et seq. and 39-3601 et seq., the Idaho Department of Environmental Quality (DEQ) has authority to review activities receiving federal permits and issue water quality certification decisions.

In accordance with the Clean Water Act §§ 121.4 and 121.5, all project proponents must submit a request for a pre-filing meeting at least thirty days in advance of submitting a certification request. A pre-filing meeting request was received by DEQ on 3/23/2023. DEQ reviewed the pre-filing meeting request and determined that necessary project information submitted with advance notice was sufficient to evaluate potential water quality impacts to act on the certification request within a reasonable period of time.

Based upon its review of the certification request in accordance with the Clean Water Act § 121.5 (b) and (c), received on 4/11/2023, DEQ certifies that if the permittee complies with the terms and conditions imposed by the permit and the conditions set forth in this water quality certification, then it is reasonable for DEQ to conclude that the activity will comply with water quality requirements, including applicable requirements of the Clean Water Act §§ 301, 302, 303, 306, and 307, Idaho's "Water Quality Standards" (IDAPA 58.01.02), and other appropriate water quality requirements of state law.

This certification does not constitute authorization of the permitted activities by any other state or federal agency or private person or entity. This certification does not excuse the permit holder from the obligation to obtain any other necessary approvals, authorizations or permits.

Accessibility Services: The Idaho Department of Environmental Quality will provide reasonable language access services and/or disability services for documents at no charge. To request an accommodation under Title VI of the Civil Rights Act of 1964 or Americans with Disabilities Act, contact DEQ's nondiscrimination coordinator at (208) 373-0271 or accessibility@deg.idaho.gov. Para obtener información en español, visite <https://www.deq.idaho.gov/about-us/accessibility/>.

1 Project Description

The proposed project would replace an existing culvert and bridge over Little Goose Creek, 2 miles east of Meadows, Adams County, Idaho. The existing culvert is poorly aligned with the streams flow line, causing scour and erosion. The project proposes constructing a 3-sided stiffleg culvert with a natural bottom. The new culvert would be realigned to match the creek's natural flow line and would meet the Idaho Transportation Departments (ITD) specifications for 50 and 100-year flood events. Construction would begin in spring of 2027 and is expected to be completed by November of that same year.

Temporary staging areas and best management practices (BMPs) will be implemented prior to work occurring. In-water work wouldn't begin until late June to avoid spring runoff. Prior to in-water work, the creek would be dewatered using a coffer dam, and routed through the old culvert using pipes adequate to convey a 5-year recurrence interval flooding event, to avoid construction on the new channel and culvert. During the installation of the bypass system, BMPs for erosion and sediment control would be implemented using ITDs Best Management Practice Manual. In addition to the bypass system, the proponent proposes using a sump pump in the active construction zone to ensure no water is present during construction. Water would be pumped from the construction zone and either routed through a portable tank or settling basin to remove sediment before discharging back to Little Goose Creek. As an alternative, water could be discharged to a rock attenuation pad underlined with geotextile liner. Sediment laden water would be filtered through the attenuation pad and would flow to an adjacent riparian zone. Temporary fiber waddles are proposed to be installed below the attenuation pad to reduce flow velocities and capture additional sediment not attenuated by the pad.

After installation of the new culvert, the proponent proposes installing erosion control geotextile liner across the full width of the new culvert bottom, along with riprap to prevent scouring of the new foundations. Additional riprap would be installed at the inlet and outlet of the culvert to prevent scouring upstream and downstream of the culvert. Finally, riprap will be keyed-in below the existing channel invert on new channel embankments, at a minimum depth of 3 feet or to the calculated scour depth, whichever is greater.

The project proposes the installation of suitable simulated streambed material imported to the site. Material size is determined by 50-year flood hydraulic modeling and DEQ monitoring data. Larger rock will be placed upstream and downstream from the culvert but will not be placed under. Upon completion of the new culvert, the project proponent will gradually introduce water into the newly engineered channel. BMPs will be implemented during this process to control sediment and to protect concrete curing. After water is returned to the channel, the old culvert will be backfilled. Upon completion of the roadway, temporary BMPs and construction materials will be removed from the site and post-construction BMPs will be implemented for long-term site stabilization. This includes regrading, seeding and/or planting, and revegetation of impacted wetlands.

2 Antidegradation Review

As part of its water quality standards program, Idaho has an antidegradation policy providing three levels of protection to water bodies in Idaho (IDAPA 58.01.02.051). DEQ adopted regulations to implement the antidegradation policy (IDAPA 58.01.02.052).

Tier I Protection. The first level of protection applies to all water bodies subject to Clean Water Act jurisdiction and ensures that existing uses of a water body and the level of water quality necessary to protect those existing uses will be maintained and protected (IDAPA 58.01.02.051.01; 58.01.02.052.01). Additionally, a Tier I review is performed for all new or reissued permits or licenses (IDAPA 58.01.02.052.07).

Tier II Protection. The second level of protection applies to those water bodies considered high quality and ensures that no lowering of water quality will be allowed unless necessary to accommodate important economic or social development (IDAPA 58.01.02.051.02; 58.01.02.052.08).

Tier III Protection. The third level of protection applies to water bodies that have been designated outstanding resource waters and requires that activities do not lower water quality (IDAPA 58.01.02.051.03; 58.01.02.052.09).

DEQ employs a water-body-by-water-body approach to implementing Idaho's antidegradation policy. This approach means that any water body fully supporting its beneficial uses will be considered high quality (IDAPA 58.01.02.052.05.a). Any water body not fully supporting its beneficial uses will be provided Tier I protection for that use, unless specific circumstances warranting Tier II protection are met (IDAPA 58.01.02.052.05.c). The most recent federally approved [DEQ Integrated Report](#) and supporting data are used to determine support status and the tier of protection (IDAPA 58.01.02.052.05).

2.1 Pollutants of Concern

The pollutant of concern for this project is sediment. As part of the § 401 water quality certification, DEQ requires the applicant to comply with various conditions to protect water quality and meet Idaho's water quality standards, including the water quality criteria applicable to sediment.

2.2 Receiving Water Body Level of Protection

This project is located on Little Goose Creek within the Little Salmon River subbasin assessment unit (AU) ID17060210SL010_03 (Goose and Little Goose Creeks – 3rd order section). According to the most recent federally approved [DEQ Integrated Report](#), this AU has the following designated beneficial uses: cold water aquatic life, salmonid spawning, and secondary contact recreation. In addition to these uses, all waters of the state are protected for agricultural and industrial water supply, wildlife habitat, and aesthetics (IDAPA 58.01.02.100).

According to DEQ's 2022 Integrated Report, this receiving water body AU is fully supporting its aquatic life use (IDAPA 58.01.02.052.05.a). As such, DEQ will provide Tier II protection in

addition to Tier I for aquatic life use (IDAPA 58.01.02.051.02; 58.01.02.051.01). The contact recreational use is unassessed. Therefore, DEQ must provide an appropriate level of protection on a case-by-case basis using information available at this time (IDAPA 58.01.02.052.05.b). DEQ presumes the contact recreation use to be fully supporting, based on a potential risk of bacteria inputs from land use in the Little Goose Creek watershed. As such, DEQ will provide Tier II protection in addition to Tier I for contact recreational uses (IDAPA 58.01.02.051.02; 58.01.02.051.01).

2.3 Protection and Maintenance of Existing Uses (Tier I Protection)

A Tier I review is performed for all new or reissued permits or licenses, applies to all waters subject to the jurisdiction of the Clean Water Act, and requires demonstration that existing uses and the level of water quality necessary to protect existing uses shall be maintained and protected. The numeric and narrative criteria in the water quality standards are set at levels that ensure protection of existing and designated beneficial uses.

Water bodies not supporting existing or designated beneficial uses must be identified as water quality limited, and a total maximum daily load (TMDL) must be prepared for those pollutants causing impairment. Once a TMDL is developed, discharges of causative pollutants shall be consistent with the allocations in the TMDL (IDAPA 58.01.02.055.05). Before developing the TMDL, the water quality standards require applying the antidegradation policy and implementation provisions to maintain and protect uses (IDAPA 58.01.02.055.04).

Throughout the life of the project, the applicant will implement, install, maintain, monitor, and adaptively manage best management practices (BMPs) to reduce erosion and minimize turbidity levels in receiving water bodies downstream of the project. In addition, permanent erosion and sediment controls will be implemented that will minimize or prevent future sediment contributions from the project area.

If the project is conducted according to the provisions of the project plans, federal permit, and conditions of this certification, then it is reasonable for DEQ to conclude that the project will comply with the state's numeric and narrative criteria. These criteria are set at levels that protect and maintain existing and designated beneficial uses.

There is no available information indicating the presence of any existing beneficial uses aside from those that are already designated and discussed above. The permit ensures that the level of water quality necessary to protect both existing and designated uses is maintained and protected in compliance with the Tier I provisions of IDAPA 58.01.02.051.01 and 58.01.02.052.07.

2.4 High-Quality Waters (Tier II Protection)

Little Goose Creek is considered high quality for cold water aquatic life, salmonid spawning, and secondary contact recreation. The water quality relevant to these uses must be maintained and protected, unless lowering water quality is necessary to accommodate important social or economic development.

To determine whether degradation will occur, DEQ must evaluate how the permit issuance will affect water quality for each pollutant that is relevant to aquatic life and recreation uses of Little Goose Creek (IDAPA 58.01.02.052.06). These pollutants include the following: sediment, temperature, and bacteria. BMPs for erosion and sediment control at the site are proposed by the proponent to be installed and implemented prior to any work occurring in or around the water. Additionally, all BMPs will be maintained throughout the project until construction is complete and disturbed areas are stabilized. The project will also require a Stormwater Pollution Prevention Plan (SWPPP) and Spill Prevention Plan (SPP), which will provide additional BMP guidance to prevent pollutants from entering Waters of the United States (WOTUS). During dewatering activities, the proponent will bypass the creek around active construction using a coffer dam and piping system, which will run through the existing culvert. Additionally, the proponent will keep the active construction site free of water using a sump pump when necessary. Water would be pumped from the construction zone and either routed through a portable tank or settling basin to remove sediment before discharging back to Little Goose Creek. As an alternative, water could be discharged to a rock attenuation pad underlined with geotextile liner. Sediment laden water would be filtered through the attenuation pad and would flow to an adjacent riparian zone. Temporary fiber waddles are proposed to be installed below the attenuation pad to reduce flow velocities and capture additional sediment not attenuated by the pad. These BMPs, if used properly, would eliminate sediment degradation to the existing water quality in Little Goose Creek. The proponent has proposed monitoring for turbidity when appropriate, as directed by DEQ. Impacts to water temperature may occur, resulting from the removal of riparian vegetation and nearby trees. The proponent proposes retaining trees to the greatest extent possible, but the project will likely result in reduced shading at the site. This impact is seen as temporary, and the proponent will implement revegetation and seeding practices in all impacted areas. This would include the riparian zone. Requirements for revegetation and success of revegetation efforts will ensure temperature impacts are temporary and shading is restored to its original condition. Impacts from the project are not expected to degrade bacteria levels in Little Goose Creek. Additionally, sediment impacts are expected to be minimized to an extent well below that which would cause recreational uses to be non-supporting. Therefore, proposed BMPs are expected to be sufficient for eliminating degradation relating to contact recreation in Little Goose Creek. The project complies with IDAPA 58.01.02.051.02 and IDAPA 58.01.02.052.06.

To maintain the ambient water quality conditions, permanent erosion and sediment controls must be implemented to minimize or prevent future sediment contributions from the project area. The provisions in the federal permit and the conditions of this certification ensure that degradation to Goose and Little Goose Creeks – 3rd order sections AU or Little Goose Creek will not occur. DEQ concludes that this project complies with the Tier II provisions of IDAPA 58.01.02.051.02, 58.01.02.052.06, and 58.01.02.052.08.

3 Conditions Necessary to Ensure Compliance with Water Quality Standards or Other Appropriate Water Quality Requirements of State Law

The following conditions ensure the Little Goose Creek Bridge Replacement project complies with Idaho's water quality standards and other appropriate water quality requirements of state law applicable to Little Goose Creek.

3.1 General Conditions

This certification is based on the certification request submitted by the Idaho Transportation Department on 4/11/2023 and is conditioned upon the requirement that any modification (e.g., change in work windows, etc.) of the permitted activity shall first be provided to DEQ for review to determine compliance with Idaho's water quality standards.

Because DEQ is certifying only the activity described in the certification request, this condition ensures that discharges under circumstances that differ from those described in the certification request will comply with 33 U.S.C. § 1341, 40 CFR 121, and other applicable water quality requirements, including without limitation 33 U.S.C. § 1311(a), Idaho Code § 39-108, IDAPA 58.01.02.051, IDAPA 58.01.02.052, IDAPA 58.01.02.080, IDAPA 58.01.02.200, IDAPA 58.01.02.210, IDAPA 58.01.02.250, IDAPA 58.01.02.251, IDAPA 58.01.02.252, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. DEQ reserves the right to modify, amend, or revoke this certification if DEQ determines that, due to changes in relevant circumstances—including without limitation, changes in project activities, the characteristics of the receiving water bodies, or state water quality standards—there is no longer reasonable assurance of compliance with the water quality standards or other appropriate requirements of state law.

Because DEQ is certifying only the activity described in the certification request based on information available at the time of certification, this condition ensures that discharges from activities not described in the certification request, or where there has been a change in the characteristics of or water quality standards applicable to the receiving water body, will comply with 33 U.S.C. § 1341, 40 CFR 121, and other applicable water quality requirements, including without limitation 33 U.S.C. § 1311(a), Idaho Code § 39-108, IDAPA 58.01.02.051, IDAPA 58.01.02.052, IDAPA 58.01.02.080, IDAPA 58.01.02.200, IDAPA 58.01.02.210, IDAPA 58.01.02.250, IDAPA 58.01.02.251, IDAPA 58.01.02.252, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

2. If ownership of the project changes, the certification holder shall notify DEQ, in writing, upon transferring this ownership or responsibility for compliance with these conditions to another person or party. The new owner/operator shall request, in writing, the transfer of this water quality certification to the new name. This condition ensures that, if ownership changes, DEQ has the minimum information to support ongoing compliance with 33 U.S.C. § 1341, 40 CFR 121, this water quality certification, and other

applicable water quality requirements, including without limitation Idaho Code § 39-108, IDAPA 58.01.02.080, and IDAPA 58.01.02.400.

3. A copy of this certification must be kept on the job site and readily available for review by any contractor working on the project and any federal, state, or local government personnel.

This condition ensures all responsible parties, including on-site contractors, are aware of and comply with this water quality certification and other applicable water quality requirements, including without limitation Idaho Code § 39-108, IDAPA 58.01.02.080, and IDAPA 58.01.02.400.

4. The applicant is responsible for all work done by contractors and must ensure the contractors are informed of and follow all the conditions described in this certification and the federal permit.

This condition ensures all responsible parties, including on-site contractors, comply with this water quality certification and applicable water quality requirements, including without limitation Idaho Code § 39-108, IDAPA 58.01.02.080, and IDAPA 58.01.02.400.

5. If this project disturbs more than 1-acre and there is potential for discharge of storm water to waters of the state, then coverage under the [DEQ Construction General Permit Program](#) may be required.

This condition ensures that work authorized under the federal permit complies with water quality requirements prohibiting unauthorized storm water discharges, including without limitation 33 U.S.C. § 1311(a), 33 U.S.C. § 1342(p), IDAPA 58.01.02.080, and IDAPA 58.01.02.400.

3.2 Fill Material

The following conditions 3.2.1 – 3.2.3 are necessary for the protection of beneficial uses according to Idaho’s water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.200, IDAPA 58.01.02.210, IDAPA 58.01.02.250, IDAPA 58.01.02.251, IDAPA 58.01.02.252, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. Fill material subject to suspension will be free of easily suspended fine material. Only clean material may be placed as fill. If dredged material is proposed for use as fill material and there is a possibility the material may be contaminated, then the permittee must assess and characterize sediment to determine the suitability of dredge material for unconfined-aquatic placement; determine the suitability of post-dredge surfaces; and predict the effect on water quality during dredging. Sediment assessment and characterization following the procedures in the *Sediment Evaluation Framework for the Pacific Northwest* (RSET 2018) satisfies this requirement. A different assessment and characterization methodology may be used if the DEQ approves the methodology in writing.

2. Temporary fills will be removed in their entirety on or before construction completion.
3. Excavated or staged fill material must be placed so it is isolated from the water edge or wetlands and not placed where it could re-enter waters of the state.

3.3 Erosion and Sediment Control

The following conditions 3.3.1 – 3.3.10 are necessary for the protection of beneficial uses according to Idaho’s water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.200, IDAPA 58.01.02.250, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. BMPs for sediment and erosion control suitable to prevent exceedances of Idaho’s water quality standards and TMDLs shall be selected and installed before starting construction at the site. One resource to evaluate appropriate BMPs is the *Idaho Catalog of Storm Water Best Management Practices* (DEQ 2020). Other resources may also be used for selecting appropriate BMPs.
2. Permanent erosion and sediment control measures will be installed to provide long-term sediment and erosion control and prevent excess sediment from entering waters of the state.
3. Permanent erosion and sediment control measures will be installed at the earliest practicable time consistent with good construction practices and will be maintained as necessary throughout project operation.
4. Structural fill or bank protection will consist of materials that are placed and maintained to withstand predictable high flows in the waters of the state.
5. A BMP inspection and maintenance plan must be developed and implemented. At a minimum, BMPs must be inspected and maintained daily during project implementation and replaced or augmented if they are not effective.
6. All construction debris, scraps, particles, and other associated materials will be captured and properly disposed of so they cannot enter waters of the state or cause water quality degradation.
7. Disturbed areas suitable for vegetation will be seeded or revegetated to prevent subsequent soil erosion (EPA 2000).
8. Maximum fill slopes will be material that is structurally stable once placed and does not slough into the stream channel during construction, during periods before revegetation, or after vegetation is established.
9. Sediment from disturbed areas or sediment that can be tracked by vehicles onto pavement must not leave the site in amounts reasonably expected to enter waters of the state. Placement of clean aggregate at all construction entrances or exits and other BMPs such as truck or wheel washes, if needed, must be used when earth-moving equipment will be leaving the site and traveling on paved surfaces to prevent track-out.
10. Sediment settling devices will be used to remove sediments from water being pumped from the active construction area, before discharging back into Little Goose Creek or its associated wetlands. All selected sediment settling devices will be maintained and appropriately sized to ensure efficacy of the treatment throughout the project.

3.4 Turbidity

The following conditions 3.4.1 – 3.4.4 are necessary for the protection of beneficial uses according to Idaho’s water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.200.08, IDAPA 58.01.02.250.02.e, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. Sediment resulting from this activity must be mitigated to prevent violations of the turbidity standards stipulated in Idaho’s water quality standards. Any violation of this standard must be reported to the DEQ regional office immediately.
2. Containment measures such as silt curtains, geotextile fabrics, and silt fences must be implemented and properly maintained to minimize instream sediment suspension and resulting turbidity. One resource to evaluate appropriate BMPs is the *Idaho Catalog of Storm Water Best Management Practices* (DEQ 2020). Other resources may also be used for selecting appropriate BMPs.
3. All practical BMPs on disturbed banks and within the waters of the state must be implemented to minimize turbidity. Visual observation is acceptable to determine whether BMPs are functioning properly. If a sediment plume is observed, the project may be causing an exceedance of water quality standards, and the permittee must inspect the condition of the project BMPs. If the BMPs appear to be functioning improperly, then corrective action must be taken, and the permittee must modify the activity or implement additional BMPs (this may also include modifying existing BMPs).
4. If the project continues to have a visual sediment plume after BMPs have been inspected and modified, turbidity monitoring consistent with Table 1, is required.
 - a. A properly and regularly calibrated turbidimeter is required for sample collection measurements to be analyzed in the field. The turbidimeter should be calibrated before each use or according to the manufacturer’s recommendations. The calibration log should be maintained and made available to DEQ upon request. Instantaneous grab samples may be collected for field analysis and taken to a laboratory for analysis as needed. When turbidity monitoring is required, a grab sample must be collected at an undisturbed area immediately upstream from the in-water disturbance or discharge to establish background turbidity levels. Background turbidity, latitude/longitude, date, and time must be recorded before monitoring downstream. A sample must be collected immediately downstream from the in-water disturbance or point of discharge and within the visible sediment plume. The turbidity, latitude/longitude, date, and time must be recorded for each sample. The downstream sample must be taken immediately following the upstream sample to obtain meaningful and representative results.
 - b. Results from the downstream sampling location must be compared to the upstream sample location or background turbidity to determine whether project activities are causing an exceedance of Idaho’s water quality standards. If the downstream turbidity is 50 nephelometric turbidity units (NTUs) or greater than the upstream turbidity, then the project is causing an exceedance of the water quality standards.

- Any exceedance of the turbidity standard must be reported to the appropriate DEQ regional office within 24-hours of the sample event.
- c. Earth-disturbing activities may continue once turbidity readings return to within 50 NTU over background instantaneously, or if turbidity has exceeded 25 NTU over background for more than 10 consecutive days, once turbidity readings have no longer exceeded 25 NTU over background for at least 24 consecutive hours.
 - d. Copies of daily logs for turbidity monitoring must be available to DEQ upon request. The report must describe all exceedances and subsequent corrective actions taken, including the effectiveness of the action.

Table 1. Turbidimeter monitoring and sampling when a plume is observed.

Turbidity Above Background ^a	Monitoring/Sampling Frequency ^a	Additional Actions Required
0 to 24 NTU	Visual monitoring every 2 hours	None
25 to 49 NTU	Sample every 2 hours	STOP work after 8 hours in every 24-hour period
25 NTU for 10 or more consecutive days	Sample before and after following instructions ^b	STOP work and follow instructions ^b ; notify DEQ regional office
50 NTU or more	Sample before and after following instructions ^c	STOP work and follow instructions ^c ; notify DEQ regional office

- a. Sample and report turbidity three times at each location. Use the maximum value of three samples to determine compliance following Table 1 directions.
- b. Instructions: If BMPs appear to be functioning properly, then the permittee must modify the activity or implement corrective action such as installing additional BMPs (this may include modifying existing BMPs) until additional sampling indicates turbidity standards are met. Sampling can cease when a sediment plume is no longer observed. Work can commence when a sediment plume is no longer observed, and measurements are consecutively below 25 NTU.
- c. Instructions: If BMPs appear to be functioning properly, then the permittee must modify the activity or implement corrective action such as installing additional BMPs (this may include modifying existing BMPs) until additional sampling indicates turbidity standards are met. Sampling can cease when a sediment plume is no longer observed. Work can commence when a sediment plume is no longer observed, and measurements are below 50 NTU.

3.5 In-Water Work

The following conditions 3.5.1 – 3.5.12 are necessary for the protection of beneficial uses according to Idaho’s water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.200, IDAPA 58.01.02.250, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. Work in open water must be kept to a minimum and only when necessary. Equipment shall work from an upland site to minimize disturbance of waters of the state. If this is not practicable, take appropriate measures to ensure disturbance to the waters of the state is minimized.
2. Construction affecting the bed or banks shall occur only during periods of low flow.
3. Fording the channel is not permitted. Build temporary bridges or other structures if crossings are necessary.
4. Temporary crossings shall be perpendicular to channels and located in areas with the least impact. The temporary crossings must be supplemented with clean gravel or treated with other mitigation methods at least as effective in reducing impacts. Temporary crossings must be removed as soon as possible after the project is completed or the crossing is no longer needed.

5. Heavy equipment working in wetlands shall be placed on mats or suitably designed pads to prevent damage to the wetlands.
6. Activities in spawning areas shall be avoided to the maximum extent practicable.
7. Work in waters of the state shall be restricted to areas specified in the application.
8. Prior to installation of a diversion dam, all necessary BMPs shall be implemented to eliminate erosion and sediment impacts downstream.
9. Materials used to construct the diversion dam shall be impermeable in order to eliminate water flowing in the active construction area. The dam shall be appropriately sized for the 5-year recurrence interval flow used in the pipe bypass system and will be maintained daily throughout the project.
10. Measures shall be taken to prevent wet concrete from entering waters of the state when placed in forms and/or from truck washing.
11. Stranded fish found in dewatered segments will be immediately moved to a location (preferably downstream) with water.
12. To minimize sediment transport, stream channel or streambank stabilization must be completed before returning water to a dewatered segment.

3.6 Vegetation Protection and Restoration

The following conditions 3.6.1 – 3.6.4 are necessary for the protection of beneficial uses according to Idaho’s water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.200, IDAPA 58.01.02.250, IDAPA 58.01.02.253, and IDAPA 58.01.02.400.

1. To the maximum extent practical, staging areas and access points should be placed in open, upland areas.
2. Fencing and other protective barriers should be used to mark the construction areas.
3. Where possible, alternative equipment should be used (e.g., spider hoe or crane).
4. If authorized work results in unavoidable vegetative disturbance, native riparian and wetland vegetation shall be successfully reestablished to benefit water quality at pre-project levels or improved at the completion of authorized work.

3.7 Management of Hazardous or Deleterious Materials

The following conditions 3.7.1 – 3.7.9 are necessary for the protection of beneficial uses according to Idaho’s water quality standards, including without limitation IDAPA 58.01.02.051, IDAPA 58.01.02.080, IDAPA 58.01.02.200, IDAPA 58.01.02.400, IDAPA 58.01.02.800, and IDAPA 58.01.02.850.

1. Petroleum products and hazardous, toxic, and/or deleterious materials shall not be stored, disposed of, or accumulated adjacent to or in the immediate vicinity of waters of the state. Adequate measures and controls must ensure that those materials will not enter waters of the state because of high water, precipitation runoff, wind, storage facility failure, accidents in operation, or unauthorized third-party activities.
2. Secondary containment is required for chemical materials.
3. Vegetable-based hydraulic fluid should be used on equipment operating in or directly adjacent to the channel if this fluid is available.

4. Daily inspections of all fluid systems on equipment to be used in or near waters of the state shall ensure no leaks or potential leaks exist before equipment use. A logbook of daily equipment inspections shall be kept on site and provided to DEQ upon request.
5. Equipment and machinery shall be removed from the vicinity of the waters of the state before refueling, repair, and/or maintenance.
6. Equipment and machinery shall be steam cleaned of oils and grease in an upland location or staging area with appropriate wastewater controls and treatment capability before entering waters of the state. Any wastewater or wash water must not enter waters of the state.
7. Emergency spill response procedures shall be in place and include a spill response kit (e.g., oil absorbent booms or other equipment).
8. If an unauthorized release of hazardous material to state waters or to land occurs and there is a likelihood it will enter state waters, the responsible persons in charge must:
 - a. Make every reasonable effort to abate and stop a continuing spill.
 - b. Make every reasonable effort to contain spilled material so it will not reach surface or ground waters of the state.
 - c. Call 911 if immediate assistance is required to control, contain, or clean up the spill. If no assistance is needed in cleaning up the spill, contact the appropriate DEQ regional office during normal working hours or Idaho State Communications Center after normal working hours (1-800-632-8000). If the spilled volume is above federal reportable quantities, contact the National Response Center (1-800-424-8802).
 - d. Contact Boise Regional Office: (208) 373-0550.
9. Collect, remove, and properly dispose of spill and cleanup materials in a manner approved by DEQ.

3.8 Culverts

The following conditions 3.8.1 – 3.8.6 to control erosion, sediment, and turbidity are necessary for the protection of beneficial uses according to Idaho’s water quality standards, including without limitation IDAPA 58.01.02.200 and IDAPA 58.01.02.250.

1. To prevent road surface and culvert bedding material from entering a stream, culvert crossings must include BMPs to retain road base and culvert bedding material. For perennial waters, the permittee should consider Idaho’s “Stream Channel Alterations Rules” (IDAPA 37.03.07). Another source of BMPs for culvert installation are found in the “Rules Pertaining to the Idaho Forest Practices Act” (IDAPA 20.20.01). Examples of BMPs include, but are not limited to: parapets, wing walls, inlet and outlet rock armoring, compaction, suitable bedding material, antiseep barriers such as bentonite clay, or other acceptable roadway retention systems.
2. The culvert must not constrict the stream channel and shall not be angled so the outflow is directed toward the streambank. The culvert’s flow line shall match the existing stream invert at its entrance and exit. Adequate grade control must be installed to prevent channel down cutting or excessive deposition from occurring.
3. The culvert shall be installed so it does not impede fish passage.

4. The culvert outflow shall be armored with riprap to provide erosion control. This riprap will be clean, angular, dense rock that is free of fines and resistant to aquatic decomposition.
5. Culverts shall be sized appropriately to maintain the natural drainage patterns.
6. The existing culvert and associated materials shall be removed in its entirety and disposed of appropriately.

3.9 Treated Wood

The following condition meets Idaho's water quality standards, including without limitation IDAPA 58.01.02.200 and IDAPA 58.01.02.210.

This condition ensures that toxic chemicals are not introduced into waters of the state. The *Guidance for the Use of Wood Preservatives and Preserved Wood Products In or Around Aquatic Environments* (DEQ 2008) must be considered when using treated wood materials in the aquatic environment. The DEQ guidance references the *Best Management Practices for the Use of Treated Wood in Aquatic and Wetland Environments* (Western Wood Preservers Institute et al. 2011). This BMP document provides recommended guidelines for producing and installing treated wood products for use in sensitive environments.

3.10 Dredge Material Management

Upland disposal of dredged material must prevent the material from reentering waters of the state.

This condition ensures that there is no unauthorized discharge from upland disposal sites according to 33 U.S.C. § 1311(a) and Idaho's water quality requirements, including without limitation Idaho Code § 39-108, IDAPA 58.01.02.080, and IDAPA 58.01.02.400

3.11 Pollutants/Toxins

In conformance with IDAPA 58.01.02.200, the use of chemicals such as soil stabilizers, dust palliatives, sterilants, growth inhibitors, fertilizers, and deicing salts during construction and operation should be limited to the best estimate of optimum application rates. All reasonable measures shall be taken to avoid excess application and introduction of chemicals into waters of the state.

4 Required Notification

The permittee must notify the Boise Regional Office when authorized work begins.

5 Right to Appeal Final Certification

The final § 401 Water Quality Certification may be appealed by submitting a petition to initiate a contested case, pursuant to Idaho Code § 39-107(5) and the “Rules of Administrative Procedure before the Board of Environmental Quality” (IDAPA 58.01.23), within 35-days of the date of the final certification.

Questions or comments regarding the actions taken in this certification should be directed to Chase Cusack, Boise Regional Office at (208) 373-0490 or via email at Chase.Cusack@deq.idaho.gov.



Aaron Scheff
Regional Administrator
Boise Regional Office

References

- DEQ (Idaho Department of Environmental Quality). 2008. *Guidance for the Use of Wood Preservatives and Preserved Wood Products in or Around Aquatic Environments*. Boise, ID: DEQ. <https://www2.deq.idaho.gov/admin/LEIA/api/document/download/4838>
- DEQ (Idaho Department of Environmental Quality). 2020. *Idaho Catalog of Storm Water Best Management Practices*. Boise, ID: DEQ. <https://www.deq.idaho.gov/water-quality/wastewater/storm-water/>
- DEQ (Idaho Department of Environmental Quality). 2022. *Idaho Department of Environmental Quality 2022 Integrated Report*. Boise, ID: DEQ. <https://www2.deq.idaho.gov/admin/LEIA/api/document/download/16619>
- EPA (US Environmental Protection Agency). 2000. *National Menu of Best Management Practices (BMPs) for Stormwater*. <https://www.epa.gov/npdes/national-menu-best-management-practices-bmps-stormwater>
- RSET (Northwest Regional Sediment Evaluation Team). 2018. *Sediment Evaluation Framework for the Pacific Northwest*. Prepared by the RSET Agencies.
- Western Wood Preservers Institute, Wood Preservation Canada, Southern Pressure Treaters' Association, and Southern Forest Products Association. 2011. *Best Management Practices: For the Use of Treated Wood in Aquatic and Wetland Environments*. Vancouver, WA: Western Wood Preservers Institute.