



STATE OF IDAHO
DEPARTMENT OF
ENVIRONMENTAL QUALITY

1410 North Hilton • Boise, Idaho 83706-1255 • (208) 373-0502

Dirk Kempthorne, Governor
C. Stephen Allred, Director

July 15, 2004

Certified Mail No. 7000 1670 0013 8129 0560

Patrick Clark
Environmental Advisor
Jack B. Parson Companies
P.O. Box 3429
Ogden, UT 84409

RE: Facility ID No.777-00340, Jack B. Parson Companies, Portable
Final Permit Letter

Dear Mr. Clark:

The Idaho Department of Environmental Quality (DEQ) is issuing Permit to Construct (PTC) Number P-040302 for Jack B. Parson Companies in accordance with IDAPA 58.01.01.200 through 228 (*Rules for the Control of Air Pollution in Idaho*). This permit is effective immediately and is based on your permit application received on March 16, 2004.

This permit does not release Jack B. Parson Companies from compliance with all other applicable federal, state, or local laws, regulations, permits, or ordinances.

A representative of the Pocatello Regional Office will contact you regarding a meeting with DEQ to discuss the permit terms and requirements. DEQ recommends the following representatives attend the meeting: your facility's plant manager, responsible official, environmental contact, and any operations staff responsible for day-to-day compliance with permit conditions.

Pursuant to IDAPA 58.01.23, you, as well as any other entity, may have the right to appeal this final agency action within 35 days of the date of this decision. However, prior to filing a petition for a contested case, I encourage you to call Dan Pitman at (208) 373-0502 to address any questions or concerns you may have with the enclosed permit.

Sincerely,

A handwritten signature in black ink that reads "Martin Bauer". The signature is written in a cursive, flowing style.

Martin Bauer, Administrator
Air Quality Division

MB/DH/sd

Permit No. P-040302

Enclosures

c Laurie Kral, EPA Region 10
Mark Dietrich, Pocatello Regional Office
Dan Pitman, Permit Coordinator



Air Quality
PERMIT TO CONSTRUCT
State of Idaho
Department of Environmental Quality

PERMIT NO.: P-040302

FACILITY ID No. 777-000340

SIC: 3273

UTM COORDINATE (km): Portable

1. PERMITTEE

Jack B. Parson Companies

2. PROJECT

Portable Concrete Batch Plant

3. MAILING ADDRESS

P.O. Box 3429

CITY

Ogden

STATE

UT

ZIP

84409

4. FACILITY CONTACT

Patrick Clark

TITLE

Environmental Advisor

TELEPHONE

(801) 409-2415

5. RESPONSIBLE OFFICIAL

Chuck Lindsay

TITLE

General Manager

TELEPHONE

(208) 232-5796

6. EXACT PLANT LOCATION

Portable

COUNTY

Portable

7. GENERAL NATURE OF BUSINESS & KINDS OF PRODUCTS

Concrete Manufacturing

8. GENERAL CONDITIONS

This permit is issued according to IDAPA 58.01.01.200, *Rules for the Control of Air Pollution in Idaho*, and pertains only to emissions of air contaminants regulated by the state of Idaho and to the sources specifically allowed to be constructed or modified by this permit.

This permit (a) does not affect the title of the premises upon which the equipment is to be located; (b) does not release the permittee from any liability for any loss due to damage to person or property caused by, resulting from, or arising out of the design, installation, maintenance, or operation of the proposed equipment; (c) does not release the permittee from compliance with other applicable federal, state, tribal, or local laws, regulations, or ordinances; (d) in no manner implies or suggests that the Department of Environmental Quality (DEQ) or its officers, agents, or employees, assume any liability, directly or indirectly, for any loss due to damage to person or property caused by, resulting from, or arising out of design, installation, maintenance, or operation of the proposed equipment.

This permit is not transferable to another person, place, or piece or set of equipment. This permit will expire if construction has not begun within two years of its issue date or if construction is suspended for one year.

This permit has been granted on the basis of design information presented with its application. Changes of design or equipment may require DEQ approval pursuant to the *Rules for the Control of Air Pollution in Idaho*, IDAPA 58.01.01.200, et seq.


TONI HARDESTY, DIRECTOR
DEPARTMENT OF ENVIRONMENTAL QUALITY

DATE ISSUED: July 15, 2004

Table of Contents

ACRONYMS, UNITS, AND CHEMICAL NOMENCLATURE.....	3
1. PERMIT TO CONSTRUCT SCOPE.....	4
2. STATEWIDE REQUIREMENTS.....	5
3. PERMIT TO CONSTRUCT GENERAL PROVISIONS.....	8

ACRONYMS, UNITS, AND CHEMICAL NOMENCLATURE

DEQ	Department of Environmental Quality
IDAPA	a numbering designation for all administrative rules in Idaho promulgated in accordance with the Idaho Administrative Procedures Act
km	kilometer
O&M	operations and maintenance
PM	particulate matter
PM ₁₀	particulate matter with an aerodynamic diameter less than or equal to a nominal 10 micrometers
PTC	permit to construct
<i>Rules</i>	<i>Rules for the Control of Air Pollution in Idaho</i>
SIC	Standard Industrial Classification
UTM	Universal Transverse Mercator

AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-040302

Permittee:	Jack B. Parson Companies	Facility ID No.	Date Issued:	July 15, 2004
Location:	Portable	777-00340		

1. PERMIT TO CONSTRUCT SCOPE***Purpose***

This permit to construct (PTC) is for one concrete batching facility that meets the specifications in Table 1.1.

Regulated Sources

Table 1.1 lists all sources of regulated emissions in this PTC.

Table 1.1 REGULATED EMISSIONS SOURCES

Permit Section	Source Description	Emissions Control(s)
2, 3, 4	Concrete Batch Plant that meets the following specifications	Storage Silo Baghouse Weigh Hopper Baghouse
	Capacity: No more than 200 yd ³ /hr	
	Storage Silo Capacity: 400 tons	
	Silo Stack	
	Height At least 40 ft	
	Diameter (or equivalent) No more than 2 ft	
	Exhaust flow rate At least 1,000 cfm	
	Baghouse Efficiency At least 99%	
	Hopper Stack	
	Height At least 11 ft	
	Diameter (or equivalent) No more than 2 ft	
	Exhaust flow rate At least 4,000 cfm	
	Baghouse Efficiency At least 99%	

AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-040302

Permittee:	Jack B. Parson Companies	Facility ID No.	Date Issued:	July 15, 2004
Location:	Portable	777-00340		

2. STATEWIDE REQUIREMENTS

The permittee shall comply with the following conditions when the concrete batch plant is operated anywhere (nonattainment, attainment, or unclassifiable areas) within the state of Idaho.

Emissions Limits**2.1 Opacity Limit**

Emissions emanating from any stack, vent, or other functionally equivalent opening shall not exceed 20% opacity for a period or periods aggregating more than three minutes in any 60-minute period as required in IDAPA 58.01.01.625. Opacity shall be determined using the procedures contained in IDAPA 58.01.01.625.

Operating Requirements**2.2 Facility Throughput Limits**

The production rate of the concrete batch facility shall not exceed the following rates when operating in any attainment or unclassifiable area:

- 3,000 cubic yards per day
- 200,000 cubic yards per consecutive 12-month period

2.3 Reasonable Control of Fugitive Emissions

All reasonable precautions shall be taken to prevent PM from becoming airborne as required in IDAPA 58.01.01.651. In determining what is reasonable, considerations will be given to factors such as the proximity of dust-emitting operations to human habitations and/or activities and atmospheric conditions that might affect the movement of particulate matter. Some of the reasonable precautions include, but are not limited to, the following:

- Use, where practical, of water or chemicals for control of dust in the demolition of existing buildings or structures, construction operations, the grading of roads, or the clearing of lands.
- Application, where practical, of asphalt, oil, water or suitable chemicals to, or covering of dirt roads, material stockpiles, and other surfaces which can create dust.
- Installation and use, where practical, of hoods, fans and fabric filters or equivalent systems to enclose and vent the handling of dusty materials. Adequate containment methods should be employed during sandblasting or other operations.
- Covering, where practical, of open-bodied trucks transporting materials likely to give rise to airborne dusts.
- Paving of roadways and their maintenance in a clean condition, where practical.
- Prompt removal of earth or other stored material from streets, where practical.

AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-040302

Permittee:	Jack B. Parson Companies	Facility ID No. 777-00340	Date Issued: July 15, 2004
Location:	Portable		

2.4 Operations and Maintenance (O&M) Manual Requirements

Within 60 days after startup, the permittee shall have developed an O&M manual for the storage silo baghouse and weigh hopper baghouse which describes the procedures that shall be followed to comply with General Provision 2 and the baghouse requirements contained in this permit. The manual shall contain, at a minimum, the manufacturers specifications for pressure drop, and a maintenance schedule. The manual shall remain onsite at all times and be made available to DEQ representatives upon request. Within 60 days after startup, the permittee shall submit a copy of the O&M manual to DEQ.

2.5 Monitoring Equipment

The permittee shall install, calibrate, maintain, and operate, in accordance with manufacturer's specifications, equipment to continuously measure the pressure differential across the baghouses.

2.6 Pressure Drop Across Baghouses

The pressure drop across the storage silo baghouse and weigh hopper baghouse shall be maintained within manufacturer and O&M manual specifications. Documentation of both manufacturer and O&M manual operating pressure drop specifications shall remain onsite at all times and shall be made available to DEQ representatives upon request.

Monitoring and Recordkeeping Requirements**2.7 Operating Parameters**

The following operating parameters shall be monitored and recorded. A compilation of the most recent two years of records shall be kept onsite and made available to DEQ representatives upon request.

- Pressure drop reading across the weigh hopper baghouse once per week while the concrete batch plant is operating
- Pressure drop reading across the storage silo baghouse once per month during months when the storage silo is filled
- Concrete production in cubic yards per day (cy/day) and cubic yards per month
- Each month the permittee shall calculate and record the total concrete production over the most recent 12-month period (cy/yr)

2.8 Reasonable Control Measures

The permittee shall conduct a weekly facility-wide inspection of potential sources of fugitive emissions, during daylight hours and under normal operating conditions to ensure that the methods used to reasonably control fugitive emissions are effective. If fugitive emissions are not being reasonably controlled, the permittee shall take corrective action as expeditiously as practicable. The permittee shall maintain records of the results of each fugitive emissions inspection. The records shall include, at a minimum, the date of each inspection and a description of the following: the permittee's assessment of the conditions existing at the time fugitive emissions were present (if observed), any corrective action taken in response to the fugitive emissions, and the date the corrective action was taken.

AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-040302

Permittee:	Jack B. Parson Companies	Facility ID No.	Date Issued:	July 15, 2004
Location:	Portable	777-00340		

Reporting Requirements**2.9 Relocation**

All existing portable equipment shall be registered. At least 10 days prior to relocation of any equipment covered by this permit, the permittee shall submit a scaled plot plan and a complete Portable Equipment Registration and Relocation Form (available on DEQ website at: www.deq.state.id.us/air/permits/ptc_perf.pdf), in accordance with IDAPA 58.01.01.500, to the following address:

PERF Processing Unit
DEQ - Air Quality
1410 N. Hilton
Boise, ID 83706-1255

AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-040302

Permittee:	Jack B. Parson Companies	Facility ID No.	Date Issued:	July 15, 2004
Location:	Portable	777-00340		

3. PERMIT TO CONSTRUCT GENERAL PROVISIONS

1. The permittee has a continuing duty to comply with all terms and conditions of this permit. All emissions authorized herein shall be consistent with the terms and conditions of this permit and the *Rules for the Control of Air Pollution in Idaho*. The emissions of any pollutant in excess of the limitations specified herein, or noncompliance with any other condition or limitation contained in this permit, shall constitute a violation of this permit and the *Rules for the Control of Air Pollution in Idaho*, and the Environmental Protection and Health Act, Idaho Code §39-101, et seq.
2. The permittee shall at all times (except as provided in the *Rules for the Control of Air Pollution in Idaho*) maintain in good working order and operate as efficiently as practicable, all treatment or control facilities or systems installed or used to achieve compliance with the terms and conditions of this permit and other applicable Idaho laws for the control of air pollution.
3. The permittee shall allow the Director, and/or the authorized representative(s), upon the presentation of credentials:
 - To enter, at reasonable times, upon the premises where an emissions source is located, or in which any records are required to be kept under the terms and conditions of this permit.
 - At reasonable times, to have access to and copy any records required to be kept under the terms and conditions of this permit, to inspect any monitoring methods required in this permit, and require stack compliance testing in conformance with IDAPA 58.01.01.157 when deemed appropriate by the Director.
4. Nothing in this permit is intended to relieve or exempt the permittee from compliance with any applicable federal, state, or local law or regulation, except as specifically provided herein.
5. The permittee shall notify DEQ, in writing, of the required information for the following events within 5 working days after occurrence:
 - Initiation of Construction - Date
 - Completion/Cessation of Construction - Date
 - Actual Production Startup - Date
 - Initial Date of Achieving Maximum Production Rate - Production Rate and Date
6. The Director may require the permittee to develop a list of operation and maintenance procedures to be submitted to DEQ. Such list of procedures shall become a part of this permit by reference, and the permittee shall adhere to all of the operation and maintenance procedures contained therein.
7. If performance testing (air emissions source test) is required by this permit, the permittee shall provide notice of intent to test to DEQ at least 15 days prior to the scheduled test date or shorter time period as approved by DEQ. DEQ may, at its option, have an observer present at any emissions tests conducted on a source. DEQ requests that such testing not be performed on weekends or state holidays.

AIR QUALITY PERMIT TO CONSTRUCT NUMBER: P-040302

Permittee:	Jack B. Parson Companies	Facility ID No.	Date Issued:	July 15, 2004
Location:	Portable	777-00340		

All performance testing shall be conducted in accordance with the procedures in IDAPA 58.01.01.157. Without prior DEQ approval, any alternative testing is conducted solely at the permittee's risk. If the permittee fails to obtain prior written approval by DEQ for any testing deviations, DEQ may determine that the testing does not satisfy the testing requirements. Therefore, at least 30 days prior to conducting any performance test, the permittee is encouraged to submit a performance test protocol to DEQ for approval. The written protocol shall include a description of the test method(s) to be used, an explanation of any or unusual circumstances regarding the proposed test, and the proposed test schedule for conducting and reporting the test.

Within 30 days following the date in which a performance test required by this permit is concluded, the permittee shall submit to DEQ a performance test report. The written report shall include a description of the process, identification of the test method(s) used, equipment used, all process operating data collected during the test period, and test results, as well as raw test data and associated documentation, including any approved test protocol.

8. The provisions of this permit are severable, and if any provision of this permit to any circumstance is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.
9. In accordance with IDAPA 58.01.01.123, all documents submitted to DEQ, including, but not limited to, records, monitoring data, supporting information, requests for confidential treatment, testing reports, or compliance certification shall contain a certification by a responsible official. The certification shall state that, based on information and belief formed after reasonable inquiry, the statements and information in the document(s) are true, accurate, and complete.