1410 N Hilton Street
Boise, ID 83706 • (208) 373-0502

Brad Little, Governor
Jess Byrne, Director

February 4, 2025

Justin Humphries, Superintendent
Rock Contractors
444 W. Karcher Road
Nampa, Idaho 83687

RE: Facility No. 777-00160, Rock Contractors 00160
PR-2008.0036, Project 63482
Nonmetallic Mineral Processing Plant Permit by Rule (PBR) Registration

Dear Mr. Humphries:

The Department of Environmental Quality (DEQ) is issuing a PBR Registration for a portable Nonmetallic Mineral Processing Plant for Rock Contractors 00160. The registration is for the following equipment:

Rock Crushers and Grinding Mills[1]

Crusher Classification	Type	Manufacturer	Serial No. / Equipment ID No.	Date of Manufacture	Capacity (T/hr)[2]
Primary	Cone	Terex	TRX380XSCO KNJ1640	2022	380
Primary	Jaw	Kolberg/Pioneer	407883	2007	200
Primary	Cone	Terex	TRXRX380-JOKEG0682	2014	380
Primary	Jaw	Terex	TRXCR024-ACOJM3923	2019	200
Secondary	Impactor	Texas	2000-133	2000	600
Secondary	Cone	Cedarapids	ZB10794	1994	240
Tertiary	Impactor	Humbolt	1001050516-3873	2000	600
Tertiary	Impactor	Remco	TR-4060-0118-113	2017	470

[1] Per 40 CFR 60.671, Capacity means the cumulative rated capacity of all initial crushers that are part of the plant. Initial crusher means any crusher into which nonmetallic minerals can be fed without prior crushing in the plant.

[2] T/hr = tons per hour

Screen Decks

Manufacturer	Physical Size (feet x feet)	No. of Decks	Serial No. / Equipment ID No.	Date of Manufacture
Terex	20 x 6	3	TRXV6203AOKN H1638	2022
El-Jay	16 x 5	3	34B0878	1987
El-Jay	16 x 5	3	34B0384	1982
El-Jay	16 x 5	3	34H1292	1992
El-Jay	16 x 5	3	NA	NA
JCI 6162-38HS	16 x 6	2	S072036	2007
El-Jay	16 x 5	3	34B0778	1984
Terex	20 x 6	3	TRXV6203	2014
Terex/Cedarapids	8 x 20	3	TRX820HSPOKJJ1143	2018
Terex	16 x 6	2	TRXS6162ADULL3427	2021

Electrical Generators

Manufacturer	Rated Output (kW)	Fuel Type
Caterpillar	460	Grade 2
Caterpillar	826	Grade 2
Caterpillar	750	Grade 2
Onan	60	Grade 2

This Permit by Rule registration is effective immediately, and replaces Permit by Rule registration PR-2008.0036, Project 63258 issued on January 26, 2024. We recommend that you maintain a copy of this letter at all sites where the registered equipment is being operated or stored.

Please be advised that the equipment operation, monitoring, and recordkeeping for this portable rock crushing equipment must comply at all times with the Rules for the Control of Nonmetallic Mineral Processing Plants in accordance with IDAPA 58.01.01.790 through 802 and the applicable portions of 40 CFR 60 Subpart OOO - Standards of Performance for Nonmetallic Mineral Processing Plants. A copy of IDAPA 58.01.01.790 through 802 is attached. The text for 40 CFR 60 Subpart OOO may be viewed at www.ecfr.gov (browse to Title 40, Part 60.670 - 676). A description of the portable rock crusher PBR program and links to PBR guidance and forms for registration, relocation, and operations monitoring are provided on DEQ's website at http://www.deq.idaho.gov.

EPA has amended 40 CFR 60 Subpart OOO - Standards of Performance for Nonmetallic Mineral Processing Plants for affected facilities which commence construction, modification, or reconstruction on or after April 22, 2008. These amendments include additional testing and monitoring, and changes to definitions and various other clarifications. You must be in compliance with the applicable portions of 40 CFR 60 Subpart OOO, including the requirement to conduct opacity testing on any new, modified, or reconstructed equipment within 60 days after achieving the maximum production rate at which the affected facility will be operated, but not later than 180 days after initial startup.

In order to fully understand the compliance requirements of this Permit by Rule and the requirements of 40 CFR 60 Subpart OOO, DEQ highly recommends that you schedule a meeting with David Luft**,** Air Quality Manager, at (208) 373-0201 to review and discuss the terms and conditions of this Permit by Rule. Should you choose to schedule this meeting, DEQ recommends the following representatives attend the meeting: your facility's plant manager, responsible official, environmental contact, and any other staff responsible for day-to-day compliance with permit conditions.

Other Air Quality Requirements

You are required to submit a portable equipment relocation form showing the initial location of the facility and an additional form each time the plant is moved to a new site of operations. DEQ requires that this form be submitted at least ten days prior to relocating the equipment. A copy of the form is enclosed for your convenience. You are also required to log the hours of operation for any electrical generator used, log all fugitive dust complaints, and log all triggers

that initiate fugitive dust control. A copy of each of those forms is also enclosed. If you have questions regarding this Permit by Rule process, please contact Zach Klotovich (208) 373-0502 or zach.klotovich@deq.idaho.gov.

Sincerely,



Mike Simon
Stationary Source Bureau Chief
Air Quality Division

Enclosures